



**PRICE LIST OF HYBRID SOLAR POWER SYSTEM 5.1KW 1 PHASE, NHA TRANG**

N0	NAME SUPPLIES	Explanation of materials	Unit	Quantity	UNIT PRICE vnd	INTO MONEY (vnd)
<b>VẬT TƯ CHÍNH</b>						
1		<p><b>Hybrid inverter</b> Model: Luxpower SNA6000 AC output rated: 6kW Standalone mode, Grid connected mode Number of MPPT: 2, Maximum number solar panel 7kWp Warranty: 2 years</p>	Unit	1	19,500,000	19,500,000
2		<p><b>Sunova Ntype topcon 575w solar panel</b> Plate Type : <b>Half-Cut Cells *</b> <b>Bifacial * Single-glass</b> Type and no. of cells: <b>Mono 144 cell (6×12)</b> Power range: <b>570W-580W</b> Performance range: <b>21.1% - 22,53%</b> Dimensions: <b>2278 mm x 1134 mm x 30 mm</b> Weight: <b>27.6kg</b> Manufacturer: <b>Sunova Solar</b></p>	Panel	9	3,850,000	34,650,000
3		<p><b>GIGABOX 5E lithium storage battery ( Communicate with inverter interface)</b> Total capacity: 5.12 kWh DOD Energy: 80% DC voltage range (V): 51.2 Capacity (Ah): 100 Dimensions DxRxC (mm): 650 x 440 x 155 Weight (kg): 42.5 Communication: RS485 and CAN 2.0</p>	Pack	2	23,500,000	47,000,000

<p>4</p>		<p><b>HYBRID system electrical cabinet</b> Control cabinet, lightning protection, automatic grid switching control, isolation and protection of solar power system</p>	<p>Set</p>	<p>4,000,000</p>
<p>5</p>		<p><b>DC wire to connect the battery</b> DC Leader Cable 4mm Conductor material: Copper, based on VDE0295/IEC60228, Class5 Insulation layer: Polyolefin Copolymer resists LSZH and ultraviolet rays, meets EN50618 standards. Normal current: DC 1000V/1800V Rated temperature: - 40°C ~ + 125°C, lifespan more than 25 years Color: Black, Red</p>	<p>Set</p>	<p>2,200,000</p>
<p>6</p>		<p><b>Solar panel support frame</b> Galvanized pat system + aluminum clamp Or Pat U clamp iron frame depending on the actual situation of the house</p>	<p>Set</p>	<p>7,000,000</p>
<p>7</p>		<p><b>AC cord 16mmx2</b> Power cables run from the machine inverter to the electrical cabinet and to the connection point CADIVI</p>	<p>Bộ</p>	<p>2,500,000</p>
<p>8</p>		<p><b>Connection system accessories</b> Electrical wiring box, HPDE conduit covering DC wire for storage battery connection, and AC cable connection accessories</p>	<p>Set</p>	<p>1,500,000</p>

9		<b>Installation work</b> Install the system	1 Times	5,000,000		
10		Transport materials to the construction site	1 Times	2,000,000		
		<b>Total</b>				125,350,000

**Note: The above prices do not include VAT, please add 10% if a VAT invoice is required**  
**The system has electricity storage so when there is a power outage, there will be electricity.**

\* Electrical systems, Newly installed are warranted for 1 year EXCEPT rat bites, human destruction or natural disasters.

\* Inverters are warranted for 2 years

**Ghi chú:**

\* The panels are warranted for 15 years according to the manufacturer's standards (No broken, dented due to impact, no sign of peeling, stamping, no heat impact causing fire)

Payment method: 30% deposit when ordering, 60% payment when the goods arrive at the warehouse and ready to be delivered to the construction site, the remaining 10% must be paid 1 week after acceptance